

# Polyethylene Nestable with Hand and Back Rails Casters 3 Step 500 Lb. Capacity Yellow

**MODEL SPN-3-YL-HR-BR-PO**

Industrial Ladders / Step Poly Nestable



## PRODUCT OVERVIEW

A poly step stool is a great asset for on the go or in a permanent setting. A lightweight design with front and side cutout handles, allow the user to easily transfer the stool to a preferred spot. The taped step surfaces ensure safe footing while traversing up and down the steps. Includes bolt on back rail, handrail, and casters. The hand rails height allows the unit to be pushed or pulled into the desired position, minimizing bending and twisting by the user. Steps can be nested to minimize footprint when not in use.

## KEY FEATURES

- Anti-slip step surface
- Low density polyethylene construction
- Easily maneuvered with attached casters
- Colored yellow for added safety and awareness

## CORE PRODUCT DATA

**ASSEMBLED WEIGHT**  
**88 lbs****ASSEMBLED SIZE**  
**25" W x 45.625" L x 68.25" H****SHIP WEIGHT**  
**126 lbs****PACKAGE 1 SIZE**  
**40" W x 64" D x 36" H****COLOR / FINISH**  
**Yellow****FREIGHT TYPE**  
**LTL Palletized****AVAILABILITY**      Available**QUICKSHIP: YES**

Products are sold through Vestil distributor partners. Contact a distributor for current pricing and ordering.

PRODUCT SPECIFICATIONS

|                                                  |              |
|--------------------------------------------------|--------------|
| Duty Rating (lbs)                                | 500          |
| Number of Steps                                  | 3            |
| Distance Between Rung/Steps (in)                 | 10-1/2       |
| Step Depth (in)                                  | 10-7/8       |
| Top Step Height From Ground (in)                 | 30-1/2       |
| ANSI Approved                                    | No           |
| ANSI Ladder Rating                               | Not Rated    |
| CSA Certified                                    | No           |
| OSHA Approved                                    | No           |
| Handrail Included                                | Yes          |
| Handrail Height (in)                             | 37-3/4       |
| Spring Loaded                                    | No           |
| Number of Casters / Wheels                       | 2            |
| Caster / Wheel Material                          | Hard Rubber  |
| Wheel Width (in)                                 | 1            |
| Wheel Diameter (in)                              | 3            |
| Overall Width (in.)                              | 25           |
| Overall Length (in.)                             | 45-5/8       |
| Overall Height (in.)                             | 68-1/4       |
| First Step Height (in.)                          | 10-1/2       |
| Second Step Height (in.)                         | 20-1/2       |
| First Step Width (in.)                           | 20-3/16      |
| Second Step Width (in.)                          | 18-7/16      |
| Third Step Width (in.)                           | 16-11/16     |
| Material                                         | Polyethylene |
| Handrail, Back Rail and Caster Attachment Method | Bolt-On      |

PRODUCT & SHIPPING REFERENCE

Shipping Point: Angola, IN 46703

Warranty:

90 Days

AVAILABLE PRODUCT RESOURCES



SCAN FOR CURRENT PRODUCT DATA

Live product page: <https://www.vestil.com/product.php?FID=1427>